



Slurry seal footway/cycle path

Length - 785m
 Width - 3.3m
 Additional area = 32m²

Realign kerbs - 1m
 Hedge cutting - 24m
 Side footway (0.5m) & dispose of material - 943m

Ironwork - Adjust 2no. stop tap c&f's
 Adjust 3no. manhole c&f's
 Adjust 8no. large manhole c&f's

White lining - 150mm cycle lane markings - 700m
 Bicycle lane symbol - 12 no.

Contour patch & Slurry Seal footway

Length - 314m
 Width - 1.8m
 Additional area = 47m²

20mm surface course - AC 6 dense surf 100/150

Replace PCC Edgings - 15m
 Realign kerbs - 2m
 Realign PCC Channels - 3m

Ironwork - Adjust 2no. stop tap c&f's
 Adjust 3no. manhole c&f's
 Adjust 3no. large manhole c&f's



PROJECT :-	MILFORD ROAD SOUTH MILFORD R&R
DRG. TITLE :-	WORKS DETAIL REVISION 1

DRAWN	RJC
CHECKED	
APPROVED/AUTHORISED	
ORIGINAL DRAWING SIZE	421 x 297 (A3)
CONTRACT DRAWING No	
Computer Filename :	

SCALE:-	1:3200
DATE:-	AUGUST 2022
DRAWING No :-	MRSM / REV 1